



Australian Government



Mo-99 at ANSTO

Michael Druce

NNSA Second Mo-99 Topical Meeting
Chicago, April 2013



Australian Mo-99 History



- ANSTO has supplied Mo-99 and Tc-99m to Australia since the late 1970's.
 - Commercial supply accelerated in the 1980's with the development of the Mk11B sterile Tc-99m generator
- Mo-99 has been manufactured by both neutron capture and fission methods.
 - MEK extraction with neutron activation used for over 10 years

Early 1980's Development

- Development work undertaken
 - Fission Mo-99
 - Gel Generator
 - Chromatographic generator
 - Sublimation generator
- Final decision driven by customer demand for large fission generator

Original Fission Mo-99 Process

Supplied Australia 1982 -2006




- Mass U-Target 240 g UO₂
- Enrichment 1.8% ²³⁵U (incr. to 2.2%)
- Average production per run 100 Ci EOP
- Low efficiency but enabled ANSTO to develop a commercial focus and to develop as a reliable supplier

Need for Increased Production

- Demand in Australia increased
 - Looked for new process
- Parameters for new process
 - Must use LEU (<20% U-235).
 - (Australia's commitment to non proliferation)
 - Must meet the requirements of Environmental Approval of OPAL
 - No increase in gaseous emissions.
 - Must be GMP compliant and safe to operate
 - Must be able to increase production levels.

Foils

- Program with Argonne to develop Mo-99 from LEU
- Development of uranium foil target
- U foils allows best utilisation of reactor volume and less volumes of waste.
- Heat Transfer Calculations
- Neutronics Calculations
- Input in Engineering design of Annular Target
- Target Assembly & Disassembly
- Manufacture Instrumented Rigs
- ARPANSA interaction
- Safety Studies
 - Review HIFAR OLC's
 - Water tunnel experiments
 - CFD studies
 - Reactor dynamic studies
- Safety submission for irradiation




Review of Project Development

- Challenges encountered
 - Acid dissolution
 - Evolution of radioiodines
 - Criticality considerations in liquid waste
 - Manufacture of foil
 - Routine manufacture of U foils was problematic
- In late 2004, the project was reviewed. It was decided that:
 - The development time for the foil project would be too long.
 - Alternative processes would be assessed.

Process Installed

Base Digestion Mo-99 Process



ANSTO Mo-99 Operations

- Has been operating since 2008
 - Process has been fully optimised.
- Initial capacity was 500 ci per week
- During Mo-99 supply crisis ANSTO developed a global perspective to Mo-99 supply and capacity was doubled
- Current capacity is 1000 six day Curies / week





OPAL reactor

LEU fuelled:

- making ANSTO a LEU/LEU Mo-99 producer

Large irradiation capacity



Global Perspective

ANM Pty Ltd

- ANSTO Nuclear Medicine (ANM) Pty Ltd; commercial subsidiary of ANSTO.
- Design, build and operate Mo-99 Plant (early 2016)
- Mo-99 Facility: 3,500 6 day Ci per week
 - Using IP licensed from NTP
 - Use of NTP Logistics network
 - Sales through Joint Venture (ANSTO and NTP)
 - Use of LEU fuel and targets
- Synroc Facility: 100-150 HIP cans/year

Securing Government investment


August 2012

Cabinet approves
\$168.8 million
investment in
ANM Project



19 September 2012

Announced by
Ambassador David
Stewart at the IAEA
General
Conference



IAEA
International Atomic Energy Agency

19 September 2012

Announced in
Parliament by
Senator the Hon
Chris Evans



Australian Government



Funding

Funding of \$168.8M secured by the Australian Government

- To be repaid by ANM Pty Ltd
- After repayment 75% dividend payment to Government
- 25% dividend payment to ANM Pty Ltd

Location



Goals Mo-99

- 3500 Ci (six day) Mo-99 per week
 - Up to 1000 Ci in any one day
- 100% reliability in Supply of Mo-99
- Wastes controlled
 - Liquid and solid wastes decay in building before transfer for treatment
 - No increase in gas emissions above current levels
- Working interfaces with other site facilities (OPAL, Waste Management, etc)
- Fully compliant with regulations
- Plant fully operational by end of 2015
 - (requires decisions to be made which will minimise delays)
 - Documentation complete
 - Operators trained and accredited
 - Maintenance and cleaning systems in place
 - Mo-99 registered for use by TGA (and overseas agencies)

Current Status

- Large engineering team working on design
 - Assistance from international consultants
- Concept Design complete
- Preliminary Engineering complete end April 2013
- Regulatory applications made
- Construction to commence early 2014



Thank You

