



SHINE: Technology and Progress


April 3, 2013

Introduction to SHINE Medical Technologies

Health. Illuminated.


- SHINE Medical Technologies™ is dedicated to being the world leader in safe, clean, affordable production of medical tracers and cancer treatment elements.
- Highest priority is safely delivering a highly reliable, high-quality supply of the medical ingredients required by nearly 100,000 patients each day

Production Device Overview



Technology Advantages


- Technology merges positive aspects from accelerators and AHRs, eliminates negatives
- DT accelerator advantages
 - Demonstrated technology, very high yield
 - Efficient and inexpensive, not self sustaining
- Subcritical aqueous target advantages
 - High multiplication while keeping safely away from critical
 - Small, bounded power changes in response to void and temperature
 - No control system “chasing” on instability
 - Cannot become critical after fill procedure completed
 - Easy separation, very low waste production
 - Minimal decay heat after shutdown; less than a hair dryer



SHINE Will Sell HSA (fission) ^{99}Mo Supply Chain

Centralized Business Model


Distributed Business Model



- SHINE produces ^{99}Mo and purifies it
- Bulk product is packaged for sale to radiopharmacies by existing generator manufacturers
- Other isotopes will also be delivered (^{131}I - ^{133}Xe , and others)


Excellent Progress Made on Driver Prototype I

- Demonstration of reliable, repeatable particle beams at 20 mA, 275 keV
 - Consistent neutron yield demonstrated
 - 400+ hours of operational runtime
 - Now deployed at Picatinny Arsenal for use in neutron radiography of munitions



Prototype II Will Develop Experience on Plant-Scale Driver

- Designed for plant-scale operations
 - Full current / voltage (50 mA, 300 kV)
 - Plant configuration (geometry)
 - Purpose is to demonstrate full output, assess long-term reliability issues
 - System now operational, repeated demonstration of well focused, full current beam



Strong Progress Continues on Development of Target Solution Vessel (TSV)

- Physical optimization complete
 - Physical dimensions / materials chosen
 - Solution chemistry and volumes locked
 - Steady state behaviors analyzed
 - Output yields determined using MCNP5/ORIGEN-S
 - Each accelerator / TSV system is capable of up to 1000 6-day Ci / wk
- Recent work has focused on operational and startup strategies
 - Startup will use solution fill to allow 1/M approach
 - Maximum multiplication occurs at startup, operational behaviors push multiplication factor downward



Additional Work has Focused on Target Related Systems

- Offgas control
 - Radiation field during process results in radiolysis of water (hydrogen / oxygen generation)
 - Passive technology catalyzes recombination back into water
 - Prototype system built, testing underway—resembles plant system design
 - Will assess recombiner efficiency under plant-like conditions
- Development of Subcritical Assembly Support Structure (SASS)
 - Additional barrier between radionuclides and rest of plant
 - Provides protection against physical insults, unforeseen corrosion
 - Allows for periodic sampling to check for leaks in TSV
- TSV safety and monitoring systems



Isotope Purification Technology Selected, Demonstrated

- Plant scale process designed, prototyped
 - Primary separation of isotopes done with ion exchange
 - Subsequent purification to use modified LEU Cintichem process
 - Hot cell process designed around chemical requirements, preliminary design complete
- Molybdenum separation efficiency demonstrated
 - > 97% recovery from uranyl sulfate solution of relevant concentration (LANL)
 - Very high recovery of uranium
 - Larger scale experiments expected on ANL mini-SHINE, subsequent LANL testing, but all indications are positive that sulfate will be workable
 - Additional testing being performed by Wisconsin Institute for Medical Research (WIMR)



Infrastructure Development

- Team moved into new testing location in Monona, WI
- Site selected after consideration of multiple locations:
Janesville WI
- Direct team has grown and now includes:
 - Nearly two dozen engineers
 - About a half dozen safety and quality staff
 - About a dozen support staff
- Key expertise added in nuclear operations and licensing
 - Over 200 years experience in nuclear ops
 - ~ 100 years experience in NRC licensing


New Test Facility (~14,000 ft², 60-40 office / lab split)



Renderings of Production Facility on Site Location (Janesville, WI)



Aerial View of Janesville Site



Frequent Engagement with NRC

- A series of preapplication meetings have covered a range of topics and we have found them to be useful:
 - Technology approach and overview
 - Content and structure of the proposed license application
 - Application submission and review structure
 - Facility designs
 - Physics and design of the subcritical assembly
 - Subcritical assembly and start-up philosophy
 - Security
 - Postulated accidents
 - Site selection
 - Environmental monitoring
 - Waste management
 - Transportation
- Thank you to NRC for agreeing to take part in this process!

NRC Environmental Report Submitted

- Represents 18 months of extensive data collection and analysis
- Covers things such as weather and groundwater data
- Migratory species movements, endangered species
- Socioeconomic studies of plant impacts on nearby communities
- Impacts of construction
- Study of plant activities impact on human environment
- **Report should kick off NRC review of SHINE construction permit application**

Exceptional Progress on Facility Design

- Conceptual design completed
- Preliminary design nearly complete
 - Represents majority of work performed since last time
 - Forms cornerstone of NRC preliminary safety analysis report, sets baseline for final design
 - Includes system descriptions, mass balances, physical layouts, shielding, structural design and seismic analysis, selection of appropriate codes and standards, and safety related system designs
- Approximate facility size ~ 55,000 ft², will house 8 TSV's, 3 hot cell trains, solution cleanup and others



Preliminary Safety Analysis Report

- Part II of submittal needed to receive CP
- Based on preliminary design and combined with safety analysis
- Considers accident scenarios, both credible and incredible (MHA)
- Includes preliminary integrated safety analysis
- Includes preliminary accident analysis
- Includes facility preliminary design documents and related analysis
- Expected to finish in April, 2013


Other Activities

- Waste handling and disposal strategy
- Development of environmental monitoring plan
- Fundraising
- Development of strategic relationships
- Preliminary interaction with FDA
- Development of quality systems and procedures
- Build up of project management infrastructure
- Preliminary discussions with construction companies
- Many other activities

Next Steps (2013-2014)

- Demonstrate accelerator reliability, assess any weak spots from long term operation and improve
- Development and lock-down of secondary plant related system
- Model process hot-cells in plywood
- Complete final design, select constructor
- Submit Final Safety Analysis Report (FSAR)
- Secure vendors for long-lead time items
- Many other subtasks

Summary Timeline



<ul style="list-style-type: none"> • Submit NRC CP application 	<ul style="list-style-type: none"> • NRC construction approval 	<ul style="list-style-type: none"> • Construction 	<ul style="list-style-type: none"> • Complete plant • Install equipment
<ul style="list-style-type: none"> • Demo prototypes 	<ul style="list-style-type: none"> • Final design / submit OL application 	<ul style="list-style-type: none"> • Early training 	<ul style="list-style-type: none"> • Testing & training
<ul style="list-style-type: none"> • Establish Drug Master File 	<ul style="list-style-type: none"> • Site preparation 	<ul style="list-style-type: none"> • Production staff up 	<ul style="list-style-type: none"> • Ramp-up production

Summary

- Excellent progress continues on many fronts:
 - Technology: continues to evolve toward production scale processes
 - Design: Conceptual design complete, preliminary design nearly complete
 - Regulatory: First part of construction permit application filed, second part will follow shortly. Preliminary interaction with FDA
 - Infrastructure: Team has expanded to ~40 very well motivated, capable staff members, strategic relationships being developed
- On track for 2016 product sales

Thank You!

Dr. Gregory Piefer
SHINE Medical Technologies, Inc.

www.SHINEmed.com
Greg.p@shinemed.com