

### NWMI Overview and Status Mo-99 Topical Meeting

Carolyn C. Haass, Chief Operating Officer September 13, 2016



### **NRC Regulatory Strategy**

Combine several license activities and submit one application that covers all applicable regulations for construction/operation of the Radioisotope Production Facility (RPF) under 10 CFR 50 and 10 CFR 70

#### 10 CFR 50 Activities

- Irradiated target receipt
- Irradiated target disassembly
- Target dissolution
- <sup>99</sup>Mo separations, purification, and packaging
- Uranium (U) recycle and recovery
- Waste management
- Associated laboratory and support
- Handling of byproduct material (integration with 10 CFR 30 activities)
- University reactor(s)and cask licensee(s) will amend their current operating licenses
- ~40 State/Local permits are required to be completed and approved prior to construction and operation of RPF





#### 10 CFR 70 Activities

- Receipt of low-enriched uranium (LEU) (from DOE)
- Production of LEU microspheres
- Target fabrication and testing
- Shipping/loading of fabricated targets

# **Primary Assumptions**

- Single Radioisotope Production Facility (RPF)
  - Use low-enriched uranium (LEU)
  - <sup>99</sup>Mo produced using a fission-based method "Gold Standard"
  - Nominal weekly capacity 3,500 6-day Ci; surge capacity of 1,500 6-day Ci
  - Recover <sup>99</sup>Mo from LEU targets using standard chemical processes
- Use network of university reactors to maximize existing infrastructures and facility
  - Use same target design for all reactors
- Recycle processed LEU for reuse as target material
- > Fission product releases will comply with environmental release criteria
- Generate Class A, B, and C wastes; no greater than Class C (GTCC) waste
- Uranium processing and storage will meet all required safeguards and security requirements





# **RPF Process Flow Diagram**



- LEU target material is fabricated (both fresh LEU and recycled U)
- Clading to Clading to Solid Waste Handling to LEU target material encapsulated using metal cladding  $\rightarrow$  LEU target
  - LEU targets are packaged and shipped to university reactors for irradiation
  - After irradiation, targets are shipped back to RPF
  - **G** Irradiated LEU targets disassembled
  - Irradiated LEU targets dissolved into a solution for processing
  - Dissolved LEU solution is processed to recover and purify <sup>99</sup>Mo
  - Purified <sup>99</sup>Mo is packaged/shipped to a radiopharmaceutical distributor
  - LEU solution is treated to recover U and is recycled back to Step 1



# **Facility Description**

- First level footprint ~52,000 ft<sup>2</sup>
  - Target fabrication area
  - Hot cell processing area (dissolution, <sup>99</sup>Mo, and <sup>235</sup>U recovery)
  - Waste management, laboratory and utility areas
- Basement ~2,000 ft<sup>2</sup> (tank hot cell, decay vault)
- Second level ~17,000 ft<sup>2</sup> (utility, ventilation, offgas equipment)
- ➢ Waste Management Building ~1,200 ft<sup>2</sup>
- Administration Building (outside of secured RPF area) ~10,000 ft<sup>2</sup>

- ➢ High bay roof 65 ft
- Mechanical area, second floor 46 ft
- Top of exhaust stack 75 ft
- ➢ Loading dock (back) roof − 20 ft
- Support and admin (front) roof 12 ft
- Depth below grade for hot cell/high-integrity container (HIC) storage – 15 ft





## **Facility Cross-Sections**





# **NWMI Project Status**

- Site selection completed Discovery Ridge Research Park (Columbia, MO)
- > RPF preliminary design and associated Integrated Design Report completed
- Construction Permit Application submitted and responded to all requests for additional information (RAI) to date
  - Preconstruction activities have been initiated
  - NRC and local regulatory authorities to be completed by late summer 2017
  - Construction to be initiated immediately after approval of NRC Construction Permit Application
- Re-evaluated all physics modeling at all University reactors and updated entire process mass and activity balances
- ➢ RPF final design initiated and will be completed in 1<sup>st</sup> Q 2017
- Initiated development of Operating License Application (Completed Summer 2017)
- General preconstruction/construction selected; activities have been initiated
- Final stages of completing ULTB contracts with DOE
- R&D activities
  - Completed 12 irradiation/processing tests (10-20 Ci/test) to date and met all required Tc generator incoming requirements (e.g., US pharmacopeia requirements)
  - Next 3-6 Months Activities
    - Produce ~500 Ci of Mo-99 on up to 8 process tests
    - Complete additional quality related generator tests (e.g., 1 20 Ci)
    - Fabricate and irradiate full-scale LEU target at Oregon State University





### **NWMI Team**

Commercial Irradiation Services University Reactors





#### Radioisotope Production Facility

#### Engineering Design





Criticality, Shielding, and Safety Analysis

**ATKINS** 

Preconstruction/Construction



Environmental Assessments and Permitting



#### Technology Demonstration





Narodowe Centrum Badań Jądrowych National Centre for Nuclear Research Świerk







