Northwest Medical Isotopes, LLC Radioisotope Production Facility Overview





⁹⁹Mo Topical Meeting

Carolyn Haass, Chief Operating Officer September 24, 2018



NWMI Project – Primary Assumptions

NWMI Mission – Establish and deliver (as soon as possible) a domestic, reliable, securable source of at least 3,000 6-day curies of ⁹⁹Mo per week, steady state and without the use of highly enriched uranium.

- ⁹⁹Mo produced by a fission-based method using LEU "Gold standard"
- Single radioisotope production facility (RPF)
 - Target fabrication, ⁹⁹Mo production, and uranium recycle and recovery
 - Nominal capacity >3,000 6-day curies (Ci); surge capacity of 1,500 6-day Ci
- \succ Use network of university reactors \rightarrow Same target design for all reactors
- Fission product releases will comply with environmental release criteria
- Generate Class A, B, and C wastes; no greater than Class C waste
- Legal and regulatory drivers define how RPF work will be performed













NWMI Project Status and Schedule

- Radioisotope Production Facility
 - Site Discovery Ridge Research Park (Columbia, MO)
 - Received ~\$7 million in tax abatements
 - Completed RPF preliminary design and initiated final design
 - 10 CFR 50 Construction Permit approved (May 2018)
 - Final EIS published by the NRC (May 2017)
 - 10 CFR 70.21 exemption EA/FONSI complete; exemption approval imminent
 - Initiated development of OLA and preconstruction activities
- Research and development
 - Completed cold and hot small-scale irradiation and processing demonstration tests
 - Completed and continuing large-scale ⁹⁹Mo production to support ^{99m}Tc generator testing
 - Completed target material production with both NU and LEU
- University research reactors
 - University reactor network identified; commercial irradiation services agreements complete
 - OSTR license amendment approved for irradiation of up to three prototypic targets (January 2016)







NWMI RPF Site and University Reactor Network Locations





Siting – Discovery Ridge Research Park (Columbia, MO)





NWMI NRC Licensing Strategy

Combine several license activities and submit one application that covers all applicable regulations for construction/operation of the RPF under 10 CFR 50

10 CFR 50 Activities

- Irradiated target receipt
- Irradiated target disassembly
- Target dissolution
- ⁹⁹Mo separations, purification, and packaging
- Uranium (U) recycle and recovery
- Waste management

University reactor(s)

and cask licensee(s)

operating licenses

will amend their current

Associated laboratory and support

10 CFR 70 Activities

- Receipt of low-enriched uranium (LEU) (from DOE)
- Production of LEU microspheres
- Target fabrication and testing
- Shipping/loading of fabricated targets
- Laboratory and support areas

10 CFR 30 Activities

- Handling of byproduct material

Administration Target fabrication area and support area LT. 88 Waste management area $\bigcirc \bigcirc \bigcirc$:0 00000 Irradiated target receipt area **Utility area** Laboratory area 10 CFR 70 10 CFR 50 NWMI-040132r01



NWMI RPF Operating Characteristics



- LEU target material is fabricated (both fresh LEU and recycled U)
- ② LEU target material encapsulated using metal cladding → LEU target
- LEU targets are packaged and shipped to university reactors for irradiation
- After irradiation, targets are shipped back to RPF
- Irradiated LEU targets disassembled
- Irradiated LEU targets dissolved into a solution for processing
- Dissolved LEU solution is processed to recover and purify ⁹⁹Mo
- Purified ⁹⁹Mo is packaged/shipped to a radiopharmaceutical distributor
- LEU solution is treated to recover U and is recycled back to Step 1



RPF Details

- First level footprint ~52,000 square feet (ft²)
 - Target fabrication area
 - Hot cell processing area (dissolution, ⁹⁹Mo, and ²³⁵U recovery)
 - Waste management, laboratory, and utility areas
- Basement ~2,000 ft² (tank hot cell, decay vault)
- Second level ~17,000 ft² (utility, ventilation, offgas equipment)
- Waste Management Building ~1,200 ft²
- Administration Building (outside secured RPF area) ~10,000 ft²

- ➢ High bay roof − 65 ft
- Mechanical area, second floor 46 ft
- Top of exhaust stack 75 ft
- ➤ Loading dock (back) roof 20 ft
- Support and admin (front) roof 12 ft
- Depth below grade for hot cell/high-integrity container (HIC) storage – 15 ft





NWMI Project Conclusions

- Complete RPF construction and initiate cold and hot startup by mid-2021 in concert with receiving NRC operating license
- Complete and obtain NRC approval for required University research reactor license amendments
- NWMI's strategy for success is threefold
 - Maintaining a realistically sustainable cost and schedule
 - Initiate operations in late 2021 and maximizing production of ⁹⁹Mo (e.g., > 3,000 Ci)
 - Reducing risk by completing necessary research and development in-concert with RPF design
- NWMI activities focus on integrating best technology and best practices from DOE, NRC, and around the world to address ⁹⁹Mo challenges while:
 - Facilitating regulatory buy-in
 - Minimizing "reinvention" investment and risk
 - Maximizing return on investment once RPF operations have been initiated





Questions?



